Typical IIP Workstation Installation

FUJIFILM

FUJI IIP Workstation



Electrical



Network

Electrical Requirements:

- ✳ Standard 110 volt outlet Required
  CPU: 110 volts, 2 Amps
  Flat Panel Monitor: 110 volts, 0.6 Amps

- ✳ 1 Network Drops
  RJ-45 connections. 100 base-T network

Physical Specifications:

- ✳ 2' 6" Minimum space during operation
  CPU: 3 3/4" H x 12 9/16" W
  Flat Panel Monitor: 16 9/64" H x 15 3/4" W

Environmental Conditions:

Temperature range: 59-86 degrees Fahrenheit
Humidity Range: 15-70% RH

✳ *Minimum requirements*





FUJIFILM Medical Systems USA, Inc.
www.fujimed.com

Version 1.0 5/14/02

Corporate Headquarters
419 West Avenue
Stamford, CT 06902-6300
203-324-2000
800-431-1850